


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

Iron COUNTY
T 42 N R 32 W

DESCRIPTION OF CORNER Section Corner 7, 8, 17, and 18
CORNER MONUMENT 1" I.D. x 36" galvanized iron pipe with 4" aluminum description cap.
DATE MONUMENT PLACED AND WITNESSED May 19, 1970
WITNESSES TO CORNER..... Cedar 6 S39°W (magnetic) 6.2 feet "S18, NBT"



Cedar 6 N41°W (magnetic) 18.5 feet "S 7, NBT"

Cedar 6 N30°W (magnetic) 10.1 feet "S 8, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 3"x3"x3½" squared cedar post in place and point of an older cedar post in the swamp peat, possibly part of the original monument. From the posts, measured out the recorded bearings and distances to the original BT's, and found remains of both trees lying under the swamp moss, with description and witness faces plain, but scribe marks obliterated.

SURVEYOR'S SEAL

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

April 26, 1971

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68