


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 42 N R 32 W

DESCRIPTION OF CORNER 1/4 corner between Sections 31 and 32
CORNER MONUMENT 1" I.D. x 36" galvanized iron pipe with 4" aluminum description cap.
DATE MONUMENT PLACED AND WITNESSED May 7, 1970
WITNESSES TO CORNER..... W. Pine 7 N65°W (magnetic) 53.4 feet "1/4S, NBT"



Red Maple 6 N73°E (magnetic) 11.5 feet "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a rusty 1" I.D. x 36" iron pipe about 25 feet SW'ly of previously calculated corner position. Found fragments of a white pine stump bearing S75°E 21 links from this pipe, corresponding to one of the original BT's. As it seemed probable that the pipe and pine fragments marked the original corner location, I accepted them as doing so.

SURVEYOR'S SEAL

SIGNED Arthur C. Enger DATE April 29, 1971
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68