


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 28, 29, 32, and 33
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED June 1, 1971
WITNESSES TO CORNER..... Red Oak 8 N19°W (mag.) 70.5 ft. "S29, NBT"



Red Oak 9 S1½°W (mag.) 78.5 ft. "S33, NBT"
Red Oak 6 N27°E (mag.) 58.2 ft. "S28, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by double proportionate measurement from corners 2 miles N, 1 mile S, 3 miles E, and 1 mile west. Corner is in a EHV power line and any original evidence was destroyed during construction.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE April 20, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68