

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 15, 16, 21, and 22

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 15, 1971

WITNESSES TO CORNER..... Red Oak 5 N41°W (mag.) 11.6 ft. "NBT"



Red Oak 6 S32°W (mag.) 22.8 ft. "NBT"

1" iron pipe N60°E (mag.) 32.2 ft.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner originally established in 1849 by random and corrected line between SE corner of Sec. 13 and SW corner of Sec. 18, supposedly at a point 240 ch. W of the first above named corner. From this point, corrected straight lines were run N and S to the corresponding corners on the N and S twp. boundaries, with intermediate corners placed on line. It appears that a 1/2 chain mistake was made either between Sec. 15 and 22, or in correcting this corner from the random line, because the alinement of found monuments (4 north and 2 south of corner) intersect the line between SE corner Sec. 13 and SW corner Sec. 18 about 80.475 ch. W'ly of SE corner of Sec. 15 (a recorded original); a 1/2 chain mistake would have been a logical amount, since the Gunter chain in use in 1849 was 1/2 chain in length. Hence, this corner was established on the S'ly extension of a line between found monuments 1/2 mile and 1 mile N, at a distance equal to the distance between those monuments, which results in an E & W and N & S alinement closely corresponding to the original method of township subdivision. This position agrees reasonably well with ties to natural features to S, N, and W of corner. Found a 1" O. D. iron pipe and wood post purporting to be this N60°E 48.7 links from corner reported herein.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE April 24, 1972

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68