

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 25, 26, 35, and 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED May 21, 1971

WITNESSES TO CORNER..... Red Pine 6 S45°E (mag.) 19.8 ft. "S36, NBT"



Jack Pine 12 N36°W (mag.) 35.3 ft. "S26, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established 300 feet due east of a WMPCo. witness monument, as indicated in company survey notes. These notes say that there was one original BT marking this location at the time the W. C. was set. No identifiable BT now, but the rotted remains of a long down pine originate from a position about at the record bearing and distance as the BT to the SE. From corner, distance E to west bank of Paint River is 5.06 ch., record distance is 4.93 ch. Found an old wood post S69°W 19 ft. for an approximate corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

April 24, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68