

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 26, 27, 34, and 35

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED May 20, 1971

WITNESSES TO CORNER..... Red Pine 20 N28½°E (mag.) 14.2 ft. "S26, NBT"



Red Pine 21 S41°W (mag.) 18.8 ft. "S34, NBT"

Red Maple 5 S71°E (mag.) 10.8 ft. "S35, NBT"

AND

Red Oak 10 N50°W (mag.) 79.7 ft. "S27, NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by double proportionate measurement from corners 1 mile S, 2 miles N, 1 mile E, and 2 miles W. Corner lies on side of a hill descending toward the west, as indicated in original field notes; about 2 chains to foot of hill.

Distances are horizontal measurements. *(Corner pipe to NBT's)*

Variation 1°38' West at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

April 24, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68