

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 41-42N R 32W

DESCRIPTION OF CORNER West 1/16 corner between Sections 4 and 33

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 14, 1971

WITNESSES TO CORNER..... Aspen 6 N8½°E (mag.) 17.8 ft. "1/16S, BT"



Red Oak 10 S78°W (mag.) 20.5 ft. "1/16S, BT"

Red Oak 6 S49°E (mag.) 26.1 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established on line between section corner 20.02 ch. W and 1/4 corner 20.02 ch. E. No evidence that the corner had been established previously.

Note: Moderate local magnetic attraction in this area. Variation 2°06' West at corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE April 25, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68