STATE OF MICHIGAN DEPARTMENT OF NATURAL RESOURCES

LAND CORNER RECORD

		COUNTY
		T 41-42N R 32W
DESCRIPTION OF CORNER _	1/4 corner between Sections	4 and 33
CORNER MONUMENT1" I.	D. x 36" iron pipe with 4" al	uminum cap.
DATE MONUMENT PLACED AND	WITNESSED May 14, 1971	
	Red Pine 6 S62°E (mag.)	29.4 ft. "1/4S, NBT"
N	Red Pine 5 N85½°E (mag.)	20.5 ft. "1/4S, NBT"
33	AND	
CIRCLE CORNER REGISTER	ED	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established on line between section corners 40.04 ch. to E and to W. Found two other monuments in vicinity: a 2" I.D. Iron pipe bearing S17½ (mag.) 14.8 ft. and a 1" I.D. iron pipe bearing S19°E (mag.) 34.9 ft., from corner re-established herein. In view of the apparent uncertainty as to the true corner location, the undersigned considered a proportionate re-establishment to be appropriate.

Important note: Strong local magnetic attraction in this area. Variation 6 20' West at corner.

SURVEYOR'S SEAL

SIGN

SIGNED ____

VOR

DATE May 1, 1972

DISTRIBUTION: REGISTERED LAND SUPVEYOR
Arthur O. Enger

County Courthouse Area Forester (Regions I & II) District or Region Surveyor Forestry Div., Lansing