


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 41-42N R 32W

DESCRIPTION OF CORNER Section Corner 3, 4, 33, and 34
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED May 14, 1971
WITNESSES TO CORNER..... Aspen 13 N32 $\frac{1}{2}$ ⁰W (mag.) 6.9 ft. "S33, NBT"



Aspen 7 S25 $\frac{1}{2}$ ⁰W (mag.) 9.6 ft. "S 4, NBT"
Aspen 9 S39⁰E (mag.) 15.6 ft. "S 3, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1" I.D. iron pipe N34⁰W (true bearing) 10.8 ft., of unknown history, but assumed it to be approximate only.

Corner re-established proportionately on line between section corners 80.08 ch. to E and to W. Position checks almost exactly with stream crossing 5.50 ch. N and with call to ascend south from corner, as mentioned in original field notes.

Important note: Strong local magnetic attraction in vicinity of corner.
Variation 11⁰30' East at corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE May 1, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68