


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 5, 6, 7, and 8
CORNER MONUMENT 1" I.D. iron pipe of unknown length, top flush with ground level
DATE MONUMENT PLACED AND WITNESSED April 28, 1970
WITNESSES TO CORNER..... Red Oak 7 S57°E (mag.) 11.6 ft. "S8, NBT"



Sugar Maple 7 N63°W (mag.) 13.5 ft. "S6, NBT"

Sugar Maple 6 S70°W (mag.) 10.6 ft. "S7, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1" I.D. iron pipe set nearly flush with ground level, to mark the corner. Accepted corner as found. Iron pipe is at an old fence corner, and checks well with an original section corner 79.923 ch. S (record distance 80.00 ch.) a stream crossing 2.56 ch. S (record: 2.50 ch.) and a stream crossing 15.14 ch. E (record 15.08 ch.)

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE May 25, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68