

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 29, 30, 31, and 32

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 23, 1970

WITNESSES TO CORNER..... (No trees or other objects available for witnesses)



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed proportionately on line between an original section corner 79.98 ch. N and a probably original 1/4 corner 39.99 ch. S, in accordance with method of original establishment. Corner falls in a gravel pit, and all direct original evidence is destroyed. However, the gravel pit is excavated from a ridge corresponding to the original record, and enough of the ridge remains to indicate that coming from the west the "top of a ridge course SW" would have been reached about 2.20 ch. W of the corner, which agrees closely with the record.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE

May 25, 1972

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68