


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY  
T 41-42N R 32W

DESCRIPTION OF CORNER Section Corner 5, 6, 31, and 32  
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap  
DATE MONUMENT PLACED AND WITNESSED April 23, 1970  
WITNESSES TO CORNER..... Balsam 7 S38°E (mag.) 23.6 ft. "S 5, NBT"



W. Pine 6 N64½°E (mag.) 37.2 ft. "S32, NBT"  
B. Spruce 5 N46½°W (mag.) 12.1 ft. "S31, NBT"  
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a Land Economic Survey wood post placed in early 1930's for an approximate corner. Reluctantly accepted the L.E.S. post as the corner, as local use of the position would probably create confusion and possible hardship if changed. L.E.S. post is plainly marked "approximate", but such posts were placed by measurement from known corners by staff compass and steel tape, with a search being made for original evidence. There is no record of any being found when the L.E.S. post was set. It is believed by the undersigned that the original corner was perhaps 40 links or so southerly of the L.E.S. post.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE

May 31, 1972

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68