

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 19, 20, 29, and 30

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 15, 1970

WITNESSES TO CORNER..... Red Pine stump S16°E (mag.) 25 lks. "NBT" (original BT stump)



Red Pine stump N 9°E (mag.) 49 lks. "S30, NBT"

White Pine 5 S63°W (mag.) 79.2 lks. "NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner relocated by reference to two original BT stumps, which were identified by measuring to the general corner location from other corners. Stumps agree in species, absolute and relative size, distance and bearing with original record, but are charred and have no visible marks. As further confirmation, I measured north 4.85 ch. and found the remains of a W. Pine 30 line tree stump, reported in the original notes as being 4.84 ch. N of the corner. Corner has been obliterated for a very long time, probably since early logging times.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

May 31, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68