

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 42N R 32W

DESCRIPTION OF CORNER 1/4 corner between Sections 19 and 20

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 7, 1970

WITNESSES TO CORNER..... W. Pine 24 N54 $\frac{1}{2}$ <sup>o</sup>W (mag.) 89.5 ft. "1/4S, NBT"



Cedar 10 N83<sup>o</sup>E (mag.) 33.8 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1/2" I.D. x 4' iron pipe S64<sup>o</sup>W 29 lks. for an approximate corner, set by unknown party, but fairly recent. Corner re-established proportionately on line between section corner 39.916 ch. N and an original line tree stump 35,087 ch. S. Position checks closely with a stream crossing S. No evidence to show that party who placed the found iron pipe had knowledge of the line tree. Distance from 1/4 corner S to an original section corner is 39.928 ch.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE

May 31, 1972

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68