


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER 1/4 corner between Sections 29 and 30
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED May 11, 1970
WITNESSES TO CORNER..... Twin Red Oaks 11 & 13 South (mag.) 68.5 ft. "NBT"



Red Maple 10 N68°W (mag.) 165.2 ft. "NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established on line between section corners 39.99 ch. to N and to S. Corner falls about 1 ch. N of an E & W fence and clearing line, which doubtless, if intended to mark the E & W 1/4 line, was erroneously established. Section corner to N is original and 1/4 cor. 1 mile S is believed to be original, but both have been obliterated for many years and apparently were not known when the fence and clearing line were constructed.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE May 31, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68