


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 17, 18, 19, and 20
CORNER MONUMENT Replaced wood post with a 1" I.D. x 36" iron pipe with 4" aluminum cap.
DATE MONUMENT PLACED AND WITNESSED April 24, 1970
WITNESSES TO CORNER..... Red Maple 6 S66½°W (mag.) 15.4 ft. "S19, NBT"



Cedar 10 S33°E (mag.) 38.7 ft. "S20, NBT"
Tamarack 11 N65°E (mag.) 41.7 ft. "S18, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 4" x 4" x 4' squared cedar post in place at an old fence and field corner. Corner perpetuated as found. The found post appears to be 30-40 years old, and the position checks well with stream crossing and swamp edge to E and with stream crossings to N and S.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

May 31, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68