

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 32 W.	C2, D2
2. PROPERTY CONTROLLING IN SECTION	5, T. 42 N. R. 32 W.	9
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 9: Not set on original survey nor subsequently apparently.

Corner C2: Original monument and accessories not found.

Corner D2: Not set on original survey; found numerous indications of approximate corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Corner 9: Established 4-29-81 during section subdivision.

Corner C2: Restored 4-30-81 by proportion between corners north and south on old north-south fence, 81 feet south of old fence west.

Corner D2: Established 4-30-81 at intersection of $\frac{1}{4}$ lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>Corner 9: Set 1" I.D.x32" iron pipe with 4" alum. cap.</p> <p>5" R. Pine S52W 10.0 ft. 1/16S,BT</p> <p>5" R. Pine N43E 4.2 ft. 1/16S,BT</p> <p>4" R. Pine S42E 11.5 ft. 1/16S,BT</p> <p>Corner C2: Set 1" I.D.x32" iron pipe</p> <p>DNR Ref. Tag and nail in:</p> <p>12" W. Spruce N09E 31.10 ft.</p> <p>4" Ash S05W 17.27 ft.</p> <p>2" Maple N26W 14.88 ft.</p>	<p>Corner D2: Set 1" I.D.x32" iron pipe</p> <p>DNR Ref. Tag and nail in:</p> <p>5" Aspen S38W 34.47 ft.</p> <p>5" Aspen N81W 37.29 ft.</p> <p>12" W. Birch N45E 19.61 ft.</p>
--	--

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-26-82

CHIEF OF SURVEY PARTY
Keith L. Sackett
MICHIGAN REGISTERED LAND SURVEYOR
Michigan Dept. of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006