

**SURVEY & REMONUMENTATION**

JAN 19 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

	<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey		T 42N R 33W	A-3 ✓
		T 42N R 34W	M-3
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

IRON COUNTY MICHIGAN  
 RECEIVED FOR RECORD  
 98 DEC 28 AM 11:14  
*L. C. Records: L. 7, P. 258*  
*Robert Stiles*  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner Sections 6 and 7, T42N, R33W  
 Section Corner Sections 1 and 12, T42N, R34W

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Gary L. Pisoni, in a field survey on Nov. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 8, 1846 by Austin Burt, U.S. Deputy Surveyor.  
 Original Corner; Sugar Post  
 Original Bearing Trees:

Lynn	12"	S 52° E	20 links (13.20 feet)
Sugar	14"	N 53° W	52 links (34.32 feet)

In October, 1851, Guy H. Carleton, U.S. Deputy Surveyor, made two new bearing trees:

Yellow Birch	10"	N 45° E	57 links (37.82 feet)
Lynn	9"	S 50° W	28 links (18.48 feet)

PEER GROUP APPROVED  
*Iron County Representative 12-18-98*  
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found a drill rod and an iron bar at corner position, set by unknown persons.

I accept the drill rod as the section corner because it has been used for surveys over the past 30 years in the area and the section lines to the East and South have been painted and blazed from this corner position and are used as timber boundary lines.

Corner record research on file with County Representative.

Distances to adjoining corners to the East and South are consistent with GLO distances.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Over the top of the existing drill rod, set a 2" diameter by 30" long split base aluminum pipe monument with a 3" aluminum cap stamped as follows: Iron County Remonumentation, T42N, R34W, R33W, S-1, S-6, S-12, S-7, 1998, RLS 27457, from which I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	12"	S 80° W	11.50 feet
Iron Bar	1 1/4" dia.	N 52° 52' 10" W	6.39 feet
Rebar	5/8" x 30"	North	4.42 feet
Sugar Maple	9"	S 28° E	30.65 feet
Steel sign post		North	4.95 feet

98-32  
 Signed by Gary L. Pisoni Date 12-21-98

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995



*L. 7 P. 258*