

RE

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Iron (County), Located In: (Town, Range, Section), and Corner Code # (A-10, M-10, etc.)

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

99 DEC 30 AM 10:30

L.C. Records: L. 8, P. 118

Handwritten signature and name of County Representative

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Quarter corner between S. 25, T42N R34W & S.30, T42N R33W

I, Gary L. Pisoni, in a field survey on December 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on September 8, 1846.

Original corner: Ironwood Post

Original bearing trees:

Table listing trees: Yellow Birch (10" S 16° E, 18 links), Sugar Maple (12" N 65° W, 27 links)

PEER GROUP APPROVED

Handwritten signature and date: 12-21-99

COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found.

In 1994, I set a P.K. Nail in the black top opposite a rock fence line running West with the intersection of a North-South County road.

I accept the intersection of an old rock fence line running West with the centerline of Pentoga County road running North and South as the best available evidence for restoring corner position.

Distances and bearings North and South along Range line from said corner check very close to G.L.O.

Corner Record Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 5/8" by 12" long rebar pin with a 3" cast aluminum cap, 6" below road bed surface, stamped to read: Iron County Remonumentation, T42N, R34W, R33W, 1/4, S-25, S-30, 1996, RLS - 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Table listing trees: Sugar Maple (8" Dbl. N 31° E, 82.48 feet), Sugar Maple (11" S 50° E, 48.39 feet), Utility Pole (#98-12233 S 28° W, 79.39 feet), Reference (3/4" x 36" aluminum), Monument (Rod with cap West, 28.00 feet), Steel Sign Post (6' West, 28.63 feet)

99-118 Signed by Gary L. Pisoni

Date 12-28-99

Surveyor's Michigan License No. 27457



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995