

SURVEY & REMONUMENTATION

JAN 19 1000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>33W</u>	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY MICHIGAN
 RECEIVED FOR RECORD
 98 DEC 28 AM 11:15
 L.C. Records: L. T. P. 264
Gary L. Pisoni
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner Sections 7, 8, 18, 17, T42N, R33W

I, Gary L. Pisoni, in a field survey on Nov. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in October, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.
 Original Corner: Wood Post
 Original Bearing Trees:
 Lynn 12" N 41° W 44 links (29.04 feet)
 Sugar 12" S 55° E 43 links (28.38 feet)

PEER CIRCLE APPROVED
Gary L. Pisoni 12-18-98
 COUNTY REPRESENTATIVE

In 1981, Gary L. Pisoni RLS found a 1" diameter iron pipe located in a four-way road intersection marking the Section corner position.
 In 1991, during the course of a private survey, I discovered that the iron pipe was destroyed due to the rebuilding of County Road 424. I reset the Section corner position with a P.K. nail from the previous ties to two reference objects (utility poles).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found the above described P.K. nail marking corner position located in the centerline of a North/South county road and 4' South of the centerline of an East/West county road.

I accept the P.K. nail as the best available evidence for restoring the corner position. P.K. nail has been used for various surveys in the surrounding sections.

Distances to adjoining corners are consistent with GLO distances.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described corner position, I set two reference monuments, being a 5/8" diameter by 30" long rebar pin, with a 3" aluminum cap stamped as follows: Iron County Remonumentation, T42N, R33W, R.M., S-7, S-8, S-18, S-17, S 40° E, 48.98 feet, 1998, RLS 27457; T42N, R33W, R.M., S-7, S-8, S-18, S-17, S 46°W, 53.77 feet, 1998, RLS 27457, from which the following reference objects bear:

R.M.	5/8" x 30" rebar	N 40° W	48.98 feet
R.M.	5/8" x 30" rebar	N 46° E	53.77 feet
	Utility Pole #97-01475	S 48° E	48.42 feet
	Utility Pole #97-01447	S 37° W	9.82 feet
	Steel sign post	N 40° W	49.6 feet

98-50
 Signed by Gary L. Pisoni
 Surveyor's Michigan License No. 27457

Date 12-21-98



L. T. P. 264