

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>33W</u>	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD**

98 DEC 28 AM 11:16

L.C. Registrar L. T. P. 268

Gail...

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sections 9, 10, 16, 15, T42N, R33W

I, Gary L. Pisoni, in a field survey on Nov. 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5							●						
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in October, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.
Original Corner; Wood Post
Original Bearing Trees:
Sugar 14" N 55°W 28 links (18.48 feet)
Sugar 6" S 25°E 33 links (21.78 feet)

On 3/29/91, Coleman Engineering found no evidence at corner position and restored section corner by proportional measurements. Set a 1 1/4" diameter iron pipe with plastic survey cap marking corner position recorded in Plats of Certified Surveys, Liber 1, Pages 136-139 on 4/19/91.

1991 Bearing Trees:
Maple 6" N 52°W 34.86 feet
Maple 5" N 11°E 23.92 feet
Oak 12" S 22°E 24.11 feet
Oak 5" S 52°W 37.02 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found iron pipe as described above. I accept the iron pipe as the best available evidence for restoring the corner position and the following bearing trees:

Sugar Maple 8" N 52°W 34.88 feet
Sugar Maple 6" N 09°E 23.93 feet
Oak 13" S 23°E 24.13 feet

PEER GROUP APPROVED
Don A. P...
COUNTY REPRESENTATIVE

Distances to adjoining corners are consistent with GLO distances.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron pipe with a 3/4" diameter aluminum rod monument, 3 feet long with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T42N, R33W, S-9, S-10, S-15, S-16, 1998, RLS 27457 from which I established the following new blazed and scribed bearing tree: (All measurements taken to a nail in side of tree)

Red Maple 6" N 89°W 29.60 feet
Steel sign post East 0.78 feet

98-54
Signed by Gary L. Pisoni Date 12-21-98
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 21, 1971
REVISED MAY 24, 1975
REVISED JAN. 1983
REVISED OCT. 1995



L.T. P. 268