



MAR 19 1997

Stock No. 26273

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in

| | | |
|-------------------------|---------------------------|---------------|
| _____ Iron _____ | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T <u>42N</u> R <u>33W</u> | <u>H-13</u> |
| | T <u>41N</u> R <u>33W</u> | <u>H-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling | S _____ T _____ R _____ | _____ |
| in Section | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous | S _____ T _____ R _____ | _____ |
| Property in Sec. | S _____ T _____ R _____ | _____ |

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD
96 DEC 23 AM 9:12
L.C. Records L. 7, P. 67
G. L. Pisoni
REGISTERED DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner between S.34, T42N R33W & S.3, T41N R33W

Gary L. Pisoni, in a field survey on November 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt, U.S. Deputy Surveyor on July 31, 1846.
Original corner: Wood Post
Original bearing trees:
Sugar 10" N 56° E 29 links (19.14 feet)
Fir 10" S 47° W 49 links (32.34 feet)

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No original corner evidence found.
Set quarter corner by single proportionate measurement between the SW and SE section corners of Section 34, T42N, R33W.
Corner Record Research on file with County Representative.

PEER GROUP APPROVED
Iron Gary L. Pisoni 12-11-96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
At the corner position, I set a 3/4" outside diameter by 3 feet long aluminum rod monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T42N, R33W, 1/4, S-34, S-3, T41N, 1996, RLS-27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)
Aspen 6" N 38° W 24.35 feet
Aspen 8" N 29° E 30.10 feet
Aspen 6" N 85° E 20.08 feet
Aspen 9" S 88° W 37.56 feet
Steel Sign Post 6' S 55° E 1.00 feet



#96-45
Signed by Gary L. Pisoni Date 12-10-96
Surveyor's Michigan License No. 27457

L. 7 P. 67