

**SURVEY &  
REMONUMENTATION**

JAN 19 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>42N</u> R <u>33W</u>	<u>1-6</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

98 DEC 28 AM 11:25  
L.C. Records: L. 7, P. 317

*Robert Stetson*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sections 15 and 14, T42N, R33W

I, Gary L. Pisoni, in a field survey on Dec. 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established in October, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner: Wood Post  
Original Bearing Trees:

Sugar	12"	S 60° W	74 lks. (48.84 feet)
Fir	9"	N 75° E	49 lks. (32.34 feet)

PEER GROUP APPROVED  
*Robert Stetson 12-18-98*  
COUNTY REPRESENTATIVE

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of original B.T.s found.

Corner restored midway between the Northeast and Southeast Section corners of Section 15 and located on line between the Northeast corner of Section 15 and the North meander corner marked by a plat concrete monument on the North shore of Buck Lake

Distance along the Section line is consistent with GLO distance.

Corner record research on file with County Representative.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position, set a 3/4" diameter aluminum rod monument, 2" above ground surface, 3 feet long with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T42N, R33W, 1/4, S-15, S-14, 1998, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	9"	N 19°W	34.43 feet
Plat concrete monument	4" diameter	N 03°E	13.51 feet
Sugar Maple	8"	S 21°E	20.60 feet
Sugar Maple	7"	S 46°W	16.64 feet
Steel sign post		East	0.58 feet

98-58  
Signed by Gary L. Pisoni Date: 12-21-98  
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28 1971  
REVISED MAR. 14 1975  
REVISED JAN. 1983  
REVISED OCT., 1995



L.7 P. 317