

# SURVEY & REMONUMENTATION

FORM NO. 985-A



MAR 19 1997

Stock No. 26273

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T. 42N R. 33W	I-7
	T. R.	
	T. R.	
	T. R.	
2. Property Controlling in Section	S. T. R.	
	S. T. R.	
3. Miscellaneous Property in Sec.	S. T. R.	
	S. T. R.	

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

96 DEC 23 AM 9:21  
L.C. Records L. 7, P. 94  
*Gilbert Stieber*  
REGISTERED DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner 14, 15, 22 & 23, T42N R33W

I, Gary L. Pisoni, in a field survey on November 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Guy H. Carleton, U.S. Deputy Surveyor in 1851.  
Original corner: Wood Post  
Original bearing trees:  
Hemlock 22" N 34° W 19 links (12.54 feet)  
Hemlock 20" S 57° E 20 links (13.20 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found.  
In 1978, Donald D. Lappala, R.L.S., found iron pin located in South ditch line of Buck Lake Park Road marking Section corner position.  
I accept iron pin as the best available evidence for restoring corner position.  
Corner Record Research on file with County Representative.

PEER GROUP APPROVED  
*Gary L. Pisoni 12-1-96*  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Over the top of the existing iron pin, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T42N, R33W, S-15, S-14, S-22, S-23, 1996, RLS-27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

White Spruce	15"	N 50° E	84.83 feet
White Spruce	12"	S 48° E	26.20 feet
White Birch	10"	S 51° W	45.08 feet
Red Maple	6"	N 39° W	67.45 feet
Iron Pipe	3/4" dia.	S 10° E	33.57 feet
Iron Pipe	3/4" dia.	S 07° W	29.90 feet
Iron Pipe	3/4" dia.	S 26° W	33.36 feet
Steel sign post	6'	South	1.03 feet



#96-72  
Signed by *Gary L. Pisoni*

Date 12-10-96

Surveyor's Michigan License No. 27457

*L. 7 P. 94*