

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

97 DEC 23 PM 1:31
 L.C. Records L7 P. 177

Gilbert Stiles
 REGISTER OF DEEDS

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>33W</u>	<u>K-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner Common to Section 1,2,11,12, T42N, R33W

I, Gary L. Pisoni, in a field survey on November 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Original Corner established in 1851 by Guy Carleton, U.S. Deputy Surveyor.
 Original Corner: Post
 Original Bearing Trees:

Yellow Birch	10"	N 65° E	20 lks (13.20 feet)
Hemlock	12"	S 40° W	60 lks (39.60 feet)

PEER GROUP APPROVED
Gary L. Pisoni 12-19-97
 IRON COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found a 3/4" dia. Iron pipe lying at an angle and 2 feet East of a North-South fence line located in a beaver flooded swamp.

Distance to:	West 1/4 of Section 1	N 00° 31'26"E	2668.50 (meas.)	2651.22 (GLO)
	South 1/4 of Section 1	N 89° 13'28"E	2657.41 (meas.)	2616.90 (GLO)
	West 1/4 of Section 12	S 00° 52'13"E	2664.20 (meas.)	2651.22 (GLO)

I accept the iron pipe as the best available evidence for restoring the corner position.

County record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 3/4" outside diameter aluminum rod monument, 4 feet long and 12" above ground surface with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T42N, R33W, S2, S1, S11, S12, 1997, RLS 27457 from which the following bear: (measurement taken to a nail in side of tree)

Steel sign post	6"	S 80° W	1.05 feet
Steel sign post	6"	N 15° W	1.16 feet
Tamarack	16"	S 26° W	86.29 feet

97-7b
 Signed by *Gary L. Pisoni* Date December 16, 1997
 Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

