

**SURVEY & REMONUMENTATION**

**JAN 13 1998**

**SECTION**

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

97 DEC 23 PH 1:32  
L.C. Records 47 P. 186

*Gary L. Pisoni*  
REGISTERED PROFESSIONAL SURVEYOR

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Original corners in \_\_\_\_\_

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

Iron \_\_\_\_\_ (County)

Public Land Survey T 42N R 33W K-6

Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

Quarter Corner between Sections 13 and 14, T42N, R33W

Gary L. Pisoni, in a field survey on December 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14	●	13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

PEER GROUP APPROVED

*Gary L. Pisoni 12-19-97*  
IRON COUNTY REPRESENTATIVE

Description of original monument and accessories and/or subsequent restoration:  
Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.  
Original Corner: Wood Post  
Original Bearing Trees:

Hemlock	10"	S 70° E	60 lks (39.60 feet)
Tamarack	12"	N 65° W	60 lks (39.60 feet)

Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
No evidence of original B.T.s found.

Set quarter corner position in the centerline of Buck Lake Road and at midpoint between the Northeast and Southeast section corners of Section 14.

Distance to:	NE Sec corner of Sec. 14	N 00° 35'30"W	2673.83 feet (meas.)	2651.22 (GLO)
	SE Sec corner of Sec. 14	S 00° 12'13"W	2673.83 feet (meas.)	

Corner record research on file with County Representative.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
At the corner position, set a 5/8" diameter by 12" long rebar, 6" below roadbed surface with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T42N, R33W, 1/4, S14, S13, 1997, RLS 27457 from which the following bear: (measurements taken to a nail in side of tree)

Utility Pole	N68-875	N 49° E	46.30 feet
B. Spruce	9"	S 45° W	71.54 feet
R.M.	3/4"x13'rod mon.	West	36.71 feet
Red Maple	6"	N 51° W	63.69 feet
Steel sign post		West	37.2 feet

7-16b  
Signed by *Gary L. Pisoni*  
Surveyor's Michigan License No. 27457

Date December 17, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

