

**SURVEY &
REMONUMENTATION**

JAN 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PM 1:32

L.C. Records L.P. 178

Gilbert Stiles
REGISTER OF DEEDS

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>R33W</u>	<u>L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner between Sections 1 and 12, T42N, R33W

I, Gary L. Pisoni, in a field survey on December 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.
Original Corner: Wood Post
Original Bearing Trees:

Lynn	12"	S 50°W	8 lks (5.28 feet)
Lynn	12"	N 45° E	50 lks (33.00 feet)

PEER GROUP APPROVED
Gary L. Pisoni 12-19-97
IRON COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Corner position marked by a 3/4" dia. Iron pipe in a 12" x 12" concrete slab located at a fence corner.
Corner was probably set by the local mining company many years ago.

Accept the iron pipe in concrete as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a reference monument which is a 2" dia. by 30" long aluminum pipe monument, 2" above ground surface with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T42N, R33W, R.M., 1/4, S1, S12, S45° E, 3.0', 1997, RLS 27457 from which the following bear:(measurements taken to a nail in side of tree)

Black Cherry	8"	N 49° E	74.67 feet
W. Spruce	4"	S 01° E	43.21 feet
Black Cherry	6"	S 74° W	36.88 feet
R.M.	2"x30" Al. Pipe	N 45° W	3.0 feet
Steel sign post		North	1.15 feet

97-8b
Signed by Gary L. Pisoni Date December 16, 1997
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS ON 28, 1971
REVISED MAY 14, 1992
REVISED JAN 1993
REVISED OCT 1995
REGISTERED LAND SURVEYOR