

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

97 DEC 23 PM 1:32

L.C. Records L.P. 179

Gilbert J. Pisoni
 REGISTER OF DEEDS

For corners in

Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>33W</u>	<u>M-2</u>
	T <u>42N</u> R <u>32W</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner between Section 1, T42N, R33W and
 Section 6, T42N, R32W

I, Gary L. Pisoni, in a field survey on December 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by Austin Burt, U.S. Deputy Surveyor.

Original Corner: Sugar Post

Original Bearing Trees:

Sugar	16"	S 40° E	57 lks (37.62 feet)
Sugar	12"	N 50° W	18 lks (11.88 feet)

PEER GROUP APPROVED

Gary L. Pisoni 12-19-97
 IRON COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Set the quarter corner by single proportionate measurement and on line between the Northeast and Southeast corners of Section 1.

The quarter corner proportional position is approximately 1 1/2 ft. from a very old 4 way fence line intersection. Fence line is lying on ground.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the proportional position, set a 3/4" outside diameter aluminum rod monument, 18" long and flush with ground surface with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T42N, R33W, R32W, 1/4, S1, S6, 1997, RLS 27457 from which the following bear: (measurements taken to a nail in side of tree)

S. Maple	12"	N 72° E	88.32 feet
S. Maple	12"	S 70° E	91.22 feet
S. Maple	12"	S 30° W	80.24 feet
Utility Pole	74-1189	S 56° W	27.29 feet
Steel sign post		East	0.85 feet

97-9b
 Signed by *Gary L. Pisoni*

Date December 16, 1997

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN. 28, 1997

