

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 35W T 42N R 34W T ___ R ___ T ___ R ___	M-7 A-7 ✓ _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

99 DEC 30 AM 10:28  
L.C. Records: L. S. P. 108  
*L. S. P. 108*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Section Corner to Sections 13 and 24, T42N, R35W  
Section Corner to Sections 18 and 19, T42N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by William A. Burt, U.S. Deputy Surveyor.  
Original Corner; Cedar Wood Post  
Original Bearing Trees:

Yellow Birch	14"	N 35° E	11 lks (7.26 feet)
Elm	16"	S 40° W	39 lks (25.74 feet)

On October 6, 1851, Guy H. Carleton, U.S. Deputy Surveyor made the following (2) new bearing trees:

Yellow Birch	18"	S 45° E	70 lks (46.20 feet)
Sugar	10"	N 73° W	27 lks (17.82 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

At the corner position, found a 1" diameter iron pin. Iron pin was set by W. E. DeWald, a local mining engineer in the 1960's. Iron pin is consistent with GLO distances North and South along the Range line. I accept the iron pin as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Over the top of the existing iron pin, set a 2" diameter by 30" long split base aluminum pipe monument, with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T42N, R35W, R34W, S-13, S-24, S-18, S-19, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Yellow Birch	9"	N 18° E	10.40 feet
Red Maple	19"	S 46° E	25.37 feet
Balsam	10"	S 49° W	25.50 feet
Power Pole #80-24476		N 36° W	31.68 feet
Steel sign post		East	0.50 feet



99-108  
Signed by Gary L. Pisoni Date 12-28-99  
Surveyor's Michigan License No. 27457