

REMONUMENTATION

FEB 22 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

93 DEC 29 PH 2: 21

L.C. RECORDS L.G. P. 295

Gilbert Stiles
REGISTER OF DEEDS

For corners in **COMMISSION**

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 34W	M-6
	T 42N R 33W	A-6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

Quarter Corner 13-18 T42N R34-33W

I, Gary L. Pisoni, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on September 8, 1846.
Original corner: Ironwood Post
Original bearing trees:
Sugar Maple 12" S 47° E 20 links (13.20 feet)
Lynn 8" N 45° W 42 links (27.72 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by a 3/4" X 28" iron pin. Corner position has been used and accepted locally, for many years. Set an aluminum pipe monument over the top of iron pin as described below. Monument is 3" above ground surface.

This corner is accepted as the best available evidence of the position of the original corner.

Corner located on fence line running East and North and in line with centerline of a county road running South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T42N, R34W, R33W, 1/4, S-13, S-18, 1993, RLS 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Utility Pole #91-21318	N 25° E	74.63 feet
Utility Pole #91-21319	N 74° E	36.41 feet
U.S. Geological Bench Mark TT126, 1943	S 83° E	20.46 feet
5/8" X 30" Rebar Pin	S 24° E	64.54 feet
5/8" X 30" Rebar Pin	N 51° W	31.43 feet
Steel Sign Post	North	0.72 feet



Signed by Gary L. Pisoni

Date 12-28-93

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 21, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER

6 PAGE 295