

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #

(County)		
1. Public Land Survey	T 42N R 34W	MC North of G9
	T 42N R 34W	MC East of G9
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Apr 28 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(MC North of G9) Meander corner between Sections 21 and 22. Established in 1851 by Guy Carleton: "[South] on true line between 21 & 22..79.32 Intersect left bank of Brule River and set-meander post. Cedar 14 N49W 06 links, Cedar B N77E 18 links." and "[east] on true line between Sections 22 and 27. Offset East 90 links Thence South 68 links into East and West line. Therefore At 0.90 Line Leaves River and Set meander post."

(MC East of G9) Meander corner on the line between Sections 22 and 27, between G9 and H9. Established in 1851 by Guy Carleton: "[East] on true line between Sections 11 and 27 Offset East 90 links [from meander corner between 21 and 22] Thence South 68 links into East and West line. Therefore at 0.90 Line leaves River and set Meander Post. White Pine 18 N26E 08 links, Fir 10 S65E 12 links."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC North of G9) The original post and accessories were not recovered. Reestablished the corner on the Left bank of the Brule River at a position such that the configuration of the meander corners noted in the record, above, fits the observed location of the Left Bank of the Brule River and such that the distance from G7 to the MC herein recorded is equal to the record distance of 79.32 chains, adjusted by the local observed index correction (Meas. = 5210.2').

(MC East of G9) The original post and accessories were not recovered. Reestablished the corner on the Left Bank of the Brule River at a location which conforms to the record with respect to the reestablished Meander Corner between Sections 21 and 22. Distance east to H9 is 2506.45.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC) Set 1"IDx32" I.pipe with 4" MDNR cap stamped to read "WIT COR SEC 21 SEC22". Blazed, scribed, and set meas. nails in:

4" Cherry N39E 7.6' "MC BT"
 6" Aspen East 35.9' do
 13" Aspen N81W 17.4' do
 4" Aspen N09W 15.3' do

Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

(MC) Set 1"IDx32" I.pipe with 4" alum. MDNR cap stamped "WIT COR SEC 22 SEC 27". Blazed, scribed, and set measuring nails in:

5" Cherry N57E 18.4' "MC BT"
 6" Cherry N87E 37.5' do
 3" Aspen S50W 8.1' do
 5" Aspen N05W 27.8' do

Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/17/04