

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>42N</u> R <u>34W</u>	<u>H8</u>
	T <u>42N</u> R <u>34W</u>	<u>I6</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 27 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H8) Center of Section 22. Not established in the original survey.

(I6) Quarter corner common to Sections 14-15. Established in 1851 by Guy Carleton: "[north] on true line between Sections 14&15...40.00 Set Quarter post. Yellow Birch 9 N50E 22 links, Yellow Birch 10 S55W 21 links. ...80.00 Set post corner of Sections 10,11,14,15.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H8) Established the corner at the intersection of a straight line between the East and West Quarter corners with an old N-S woods road, the reestablished position also being on a line whose bearing from the North 1/4 corner is the mean of the bearings of the East and West lines of the Section.

(I6) The original post and accessories were not recovered. Found and accepted a 1" iron pipe with 1" drill rod projecting 2.5', adjacent. The monument is in accord with a 5/8" iron rod found at the SW corner of lands of Carmine, described in L 287, Page 319, Iron County Records. The monument was also found to be 2631.75' south of an Iron County monument at I5, very near to the index-corrected record distance of 2626' observed in this part of the township. Further corroborating the position, the line between I5 and I6, when produced 1/2 mile south, agrees precisely with the position shown on old RR plans from the Chicago and Northwestern Railway, which give the distance from I7 east to the Chicago Mine spur.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H8) Set 1"IDx32" I.pipe with 4" alum.

MDNR cap. Blazed, scribed, and set measuring nails in:

9" Sugar S36W 60.1' "C1/4 BT"
 6" Sugar S68W 36.4' do
 5" Sugar N54W 37.5' do
 4" Poplar S57E 12.2' do

Monument was driven to 2" below road grade. Bearings are magnetic. Distances are to nail with tag.

(I6) Found 1"ID iron pipe with drill rod adjacent. Blazed, scribed, and set measuring nails in:

10" Sugar S42W 12.3' "1/4S N8T"
 8" Sugar S85W 19.8' do
 6" Sugar N20E 7.0' do
 10" Hemlock S67E 10.3' do

Bearings are magnetic. Distances are to nail with tag. Squared a 3" Sugar S37E 2.0' to center.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/17/04

For the Michigan Department of Natural Resources, Office of Land and Facilities