

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S 21 T 42N R 34W	5	
	S 21 T 42N R 34W	7	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

Apr 26 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20 \_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (5-Sec. 21) North 1/16 corner, Section 21. Not established in the original survey.
- (7-Sec. 21) North 1/16 corner between Sections 21-22. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (5-Sec. 21) Established the corner midway and on a straight line between Center of Section (NE corner of Plat of Saunders) 1306.45' South and Quarter corner 1306.45' North. From the corner thus established, an E-W barbed wire fence is 28' north, and a N-S barbed wire fence is 125' west.
- (7-Sec. 21) Established the corner midway and on a straight line between Section corner 1313.72' North and Quarter corner 1313.72' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the

- |   |  |
|---|--|
| (5) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Blazed, scribed, and set<br>measuring nails in:<br>5" Sugar S74E 10.9'      "1/16S BT"<br>6" Sugar S24W 11.5'      do<br>6" Sugar N73W 4.4'      do<br>6" Sugar N21W 23.4'      do<br>Set sq'd cedar post adjacent. Bearings<br>are magnetic. Distances are to nail<br>with tag. | (7) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Blazed, scribed, and set<br>measuring nails in:<br>7" Sugar N16E 19.7'      "1/16S BT"<br>6" Basswood N77E 15.6'      do<br>6" Sugar S19W 28.2'      do<br>9" Sugar N69W 46.1'      do<br>Metal fence post adjacent. Bearings are<br>magnetic. Distances are to nail with<br>tag. |
|---|--|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/17/04