

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T 42N R 34W	I8
	T 42N R 34W	G7
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

G7 Apr 21 2004  
I8 Apr 20 2004

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(I8) Quarter corner common to Sections 22-23. Established in 1851 by Guy Carleton: "[south] on true line between Sections 22 and 23... 40.00 Set quarter post. Cedar 10 N72E 20 links, Sugar 8 S60W 26 links...44.76 Intersect left bank of Brule river and set Meander post." Old Chicago and Northwestern RR plans (probably ca. 1920) show distances north 255' to C/L spur to Chicagon Mine, west 140' to same, south 231' to C/L of main line.

(G7) Corner common to Sections 15-16-21-22. Established in 1851 by Guy Carleton. Set post corner of Sections 15,16,21, and 22 in edge of swamp. Aspen 16 S17W 34 links, Yellow Birch 10 N62E 10 links. Notes acquired from Gary Pisoni, PS, in 1984 show 3/4" iron pipe marking the corner and a distance to E7 of 5246.20'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(I8) The original post and accessories were not recovered. Recovered the C/L of the abandoned RR grades noted above and reestablished the corner at record distance from all, at record GLO distance, indexed, from the reestablished Meander corner on the bank of the Brule River, 313.84' south, and 2637.51' south of I7 (2640 GLO).

(G7) The original post and accessories were not recovered. Found and accepted a 3/4" iron pipe, projecting 8" above ground with a drill rod, projecting 36", driven adjacent. Distance west to E7 of 5246.77' checks well with the notes of Mr. Pisoni.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

<p>(I8) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:</p> <p>5" W.Spruce N40E 34.5'      "1/4S NBT"</p> <p>6" W.Spruce S30E 35.9'      do</p> <p>15" Hemlock S46W 37.0'      do</p> <p>5" W.Spruce N12W 11.3'      do</p> <p>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.</p>	<p>(G7) Found 3/4" iron pipe, projecting 8" above ground. Blazed, scribed, and set measuring nails in:</p> <p>6" Spruce N44E 33.9'      "S15 NBT"</p> <p>7" Spruce N80E 31.8'      do</p> <p>12" Tamarack S67W 15.4'      "S21 NBT"</p> <p>7" Tamarack N62W 39.9'      "S16 NBT"</p> <p>6'tall cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.</p>
--	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/17/04