

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>42N</u> R <u>34W</u>	<u>I7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>22</u> T <u>42N</u> R <u>34W</u>	<u>7</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Apr 20 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I7) Corner common to Sections 14-15-22-23. Established in 1851 by Guy Carleton: "[east] corrected between Sections 15 and 22...80.00 Set post corner of 14-15-22-23. Yellow Birch 20 N58W 25 links, Cedar 10 S63E 32 links. Old plans of Chicago and Northwestern RR (undated but probably ca. 1920) shows a distance to the East from this corner of 733' to a spur line labelled "to Chicagon Mine". (7-Sec. 22) North 1/16 corner between Sections 22 and 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I7) The original post and accessories were not recovered. Found an Iron County monument at I5 and a 1" I.pipe at I6 and extended that line south and reestablished I7 at the same distance from I6 as was observed between I5 and I6. From the position thus established, the distance to the center of the abandoned RR bed to the east was found to be 733'. Also from this position, the distances to 1/4 corners north, west, and south (2631.75', 2632.87', and 2637.50', respectively) all check very well with the original record (6L0=40 chains for all).

(7-Sec. 22) Established the corner midway and on a straight line between Section corner 1318.75' north and Quarter corner 1318.75' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 9" Y.Birch N65E 45.3' "S14 NBT"
 7" Sugar S41E 50.8' "S23 NBT"
 7" Maple S33W 4.8' "S22 NBT"
 9" Sugar N11W 28.4' "S15 NBT"
 Set a sq'd cedar post adjacent.
 Bearings are magnetic. Distances are to nail with tag.

(7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 6" Sugar N16E 47.5' "1/16S BT"
 10" Basswood S70E 43.7' do
 6" Sugar S26E 50.5' do
 12" W.Spruce N86W 31.9' do
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/17/04

For the Michigan Department of Natural Resources, Office of Land and Facilities