

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>42N</u> R <u>34W</u>	<u>MC East of H9</u>
	T <u>42N</u> R <u>34W</u>	<u>H9</u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

H9 Apr 27 2004
 MC Apr 28 2004

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(MC East of H9) Meander corner on the Left bank of the Brule River on the line between Sections 22 and 27, East of the Quarter corner H9. Established in 1851 by Guy Carleton... "[East] on true line between Sections 22&27...0.90 line leaves river and set meander post...40.00 set quarter post...56.68 Intersect left bank of Brule River and set meander post. Cedar 16 N43W 15 links. No other near."

(H9) Quarter corner common to Sections 22 and 27. Established in 1851 by Guy Carleton: "[East] on True line between Sections 22&27... .90 Line leaves River and set meander post...40.00 Set quarter post. Yellow Birch 10 S54E 22 links, Yellow Birch 12 N34W 13 links.... 56.68 Intersect left bank of the Brule River."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC East of H9) The original meander post and accessories were not recovered. Reestablished the corner on the Section line between Sections 22 and 27 at its intersection with the Left Bank of the Brule River. The distance observed between river banks on the line between 22 and 27 is over 200' longer than the GLO record, above. Distance west to H9 is 1345.32'.
 (H9) The original post and accessories were not recovered. Reestablished the corner at the intersection of a line run east from the west meander corner between Sections 22 and 27 (the direction of which is the mean of the bearings of several section lines in this area of the township) with the N-S 1/4 line of Section 22 (the direction of which is the mean bearing of the East and West lines of Sec. 22). A gross error appears to have been made in the original survey of the line between 22 and 27. The distance between meander corners is over 200' longer than the record. Distances west and east to monumented Meander Corners are 2506.45' and 1345.32', respectively.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC) Set 1" IDx32" I.pipe with 4" alum. MDNR cap stamped "Mit Cor Sec 22 Sec 27". Blazed, scribed, and set measuring nails in: 15" Cedar S18W 23.6' "MC BT" 7" Spruce N56W 27.5' do 8" B.Ash N22W 21.4' do 11" B.Ash S86E 13.4' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(H9) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 10" Spruce N21E 36.4' "1/4S NBT" 6" Sugar S07W 13.2' do 4" Sugar in clump S88W 22.6' do 5" twin Sugar N20W 21.7' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/17/04