

SURVEY &
REMONUMENTATION

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>35W</u>	<u>B-13</u>
	T <u>42N</u> R <u>35W</u>	<u>B-1</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:08

L.C. Records L. 8, P. 1

Gilbert L. Pisoni
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner between Section 31, T43N, R35W and
Section 6, T42N, R35W

I, Gary L. Pisoni, in a field survey on Dec. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		●											
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13		●											

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 10, 1846 by John Burt, U.S. Deputy Surveyor.
Original Corner; 5" Hemlock
Original Bearing Trees:
Sugar 6" N 80°E 17 lks (11.22 feet)

PEER GROUP APPROVED
Gary L. Pisoni 8-24-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. On 7-16-87 I set a 5/8" X 30" rebar pin at the quarter corner position by single proportionate measurement and on line between the Southeast and Southwest section corners of Section 31.

On 12-12-98 found rebar pin as previously set. I placed an aluminum cap on top of rebar pin as described below on 2/5/99.

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described corner position, I set a 3" dia. aluminum cap over the top of the existing rebar pin stamped as follows: Iron County Remonumentation, T43N, R35W, 1/4, S-31, S-6, T42N, 1999, RLS 27457, from which I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	13"	N 55°E	21.79 feet
Red Maple	8"	S 34°E	20.60 feet
Red Maple	12"	S 36°W	24.90 feet
Yellow Birch	10"	N 34°W	27.86 feet
Steel sign post		West	0.50 feet

99-01
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
No. 27457
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

