

MAR 09 2008

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>42N</u> R <u>35W</u>	<u>C-4</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:35
L.C. Records: L.S., P. 139
Gary L. Pisoni
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner to Sections 7 and 8, T42N, R35W

I, Gary L. Pisoni, in a field survey on Nov. 27, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7	●	8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 18, 1851 by Harvey Mellen, U.S. Deputy Surveyor.

Original Corner: Wood Post

Original Bearing Trees:

Sugar	12"	N 38° E	26 lks (17.16 feet)
Lynn	14"	S 70° W	19 lks (12.54 feet)

In 1982, Gary L Pisoni, RLS restored the corner position in the centerline of Marinello Road and a fence line to the West. At the corner position, set a railroad spike.

PEER GROUP APPROVED

Iron Gary L Pisoni 12-21-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found the above described railroad spike marking corner position. I accept the railroad spike as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set two (2) reference monuments being a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows:
Iron County Remonumentation, T42N, R35W, R.M., 1/4, S-7, S-8, East, 27.89 feet, 1999, RLS 27457;
T42N, R35W, R.M., 1/4, S-7, S-8, N 30° E, 52.79 feet, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees or reference objects:

Steel sign post		West	28.50 feet
R.M.	5/8" x 30" rebar	West	27.89 feet
Popple	12"	N 64° W	29.14 feet
R.M.	5/8" x 30" rebar	S 30° W	52.79 feet
Cherry	4"	S 48° E	31.78 feet

99-139
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

