

JOB NUMBER: 94314 **FEB 28 1996**

SHEET NO. : 1-551

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**IRON COUNTY MICHIGAN RECEIVED FOR RECORD**

**95 JAN 30 PM 3:51**  
L.C. RECORDS L. 6 P. 340-341

*Gilbert Stobie*  
**REGISTER OF DEEDS**

For corners in

IRON

(County)

Located In:

Corner Code #

1. Public Land Survey

T	42N	R	35W	D-1
T	43N	R	35W	D-13
T		R		
T		R		

2. Property Controlling in Section

S		T		R	
S		T		R	

3. Miscellaneous Property in Sec.

S		T		R	
S		T		R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Thursday, December 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

D-1: Quarter Corner common to Section 5, T42N-R35W and Section 32, T43N-R35W. 1846: John Burt's original survey notes describe the corner monument as a Hemlock post referenced by:  
5" Sugar Maple N15E 26 l  
26" Hemlock NS7W 39 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found a 5/8" solid iron set, according to the land owner, by a surveyor. Also, found a 1" axle shaft 2.75' above ground, set by the land owner, next to the 5/8" iron. The iron is located at the Southeast corner of a field and is on line with a woods line and old fences to the North and West, and an old fence line to the East. The position of the found iron checks well with the GLO line call, "descend hill", 5.0 chains to the East.

(SEE REVERSE SIDE FOR SKETCH)

PEER GROUP APPROVED

*Iron Larry J. Pison*  
COUNTY REPRESENTATIVE  
*A.P. 1-25-95*

C. Description of monument for corner and accessories established to perpetuate localizing the position of the corner:

1994: Replaced 5/8" iron with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet marked Iron County Remonumentation and stamped to identify the corner referenced by nails in:  
7" Maple N66E 18.24 ft.  
7" Maple S03E 24.65 ft.  
6" Maple S39W 17.11 ft.  
11" Yellow Birch N73W 11.76 ft.  
Rail with Survey Marker sign S60E 1.00 ft.  
Monument is 0.15' above ground and positioned on the Southeast side of a rock pile.



Signed by Gerald W. Carlson

Date 12-30-94

Surveyor's Michigan License No. 24589