

FEB 22 1996

JOB NUMBER: 94314
SHEET NO. : 1-553

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

95 JAN 30 PM 3: 51
L.C. RECORDS L.C. P. 342-343
Robert Stebbins
REGISTER OF DEEDS

For corners in

IRON (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 35W	F-1
	T 43N R 35W	F-13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Wednesday, December 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1: Quarter Corner common to Section 4, T42N-R35W and Section 33, T43N-R35W. 1846: John Burt's original survey notes describe the corner monument as a Sugar Maple post referenced by:
6" Sugar Maple N55E 11 1
5" Sugar Maple N62W 14 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position established equidistant and on line between the Northwest and Northeast corners of Section 4, T42N-R35W. This corner position checks well with the GLO line call "descend hill" 4 chains West and the line call "ascend hill gradually" 1 chain East.
(SEE REVERSE SIDE FOR SKETCH)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet marked Iron County Remonumentation and stamped to identify the corner referenced by nails in:
19" Sugar Maple N62W 27.78 ft.
11" Sugar Maple N23E 8.17 ft.
9" Sugar Maple S70E 8.38 ft.
5 1/2" Sugar Maple S51W 17.74 ft.
Rail with Survey Marker sign N28W 1.00 ft.
Monument is 0.3' above ground in a hardwood stand 27.8' North of old fence line.

PEER GROUP APPROVED
Iron Harry J. Poon
COUNTY REPRESENTATIVE
A.P. 1-25-95



Signed by Gerald W. Carlson Date 12-30-94
Surveyor's Michigan License No. 24589

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

