

FEB 22 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron  
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 42N R 35W

H-1

T 43N R 35W

H-13

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat

5. Private Claims

Quarter Corner 34, 3, T43N, R35W  
 T42N

I, Gary L. Pisoni, in a field survey on October 21, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, ~~re-monumented~~, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor in 1846.  
 Original corner: Ironwood Post  
 Original bearing trees:

Sugar	14"	N 75° E	4 links ( 2.64 feet)
Sugar	16"	N 36° W	36 links (23.76 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by an iron bar and located in the centerline of an East/West county road and a fence line running North. Corner position has been used and accepted as the corner locally for many years. Set an aluminum pipe monument over the top of the iron bar as described below. Monument is 6" below road bed surface.

The corner is accepted as the best available evidence of the position of the original corner.

County Record Research on file with County Representative Office.

**PEER GROUP APPROVED**

Gary L. Pisoni  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: AP. 11-30-94

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R35W, 1/4, S-34, S-3, T42N, 1994, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Rebar	5/8" x 30"	N 30° W	44.92 feet
Sugar Maple	12"	S 22° E	29.42 feet
Sugar Maple	8"	S 50° W	58.04 feet
Rebar	5/8" x 30"	N 22° E	42.03 feet
Steel Sign Post		South	24.75 feet

Signed by Gary L. Pisoni

Date 1-9-95

Surveyor's Michigan License No. 27457

REGISTER'S OFFICE )  
 IRON COUNTY, MICH. ) ..SS  
 RECEIVED FOR RECORD THE 21<sup>ST</sup> DAY OF  
FEBRUARY A.D. 19 95 AT  
2:45 O'CLOCK P. M. AND RECORDED IN LIBER  
6 OF L.C. RECORDS  
 ON PAGE 371  
Deputy REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

