

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in

<u>Iron</u> (County)	Located in:	Corner Code #	
1. Public Land Survey	T <u>42N</u> R <u>35W</u>	<u>M-7</u> ✓	
	T <u>42N</u> R <u>34W</u>	<u>A-7</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10: 28

L.C. Records: L. 8. P. 108

Gary L. Pisoni
REGISTER OF DEEDS

Registrar of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner to Sections 13 and 24, T42N, R35W
Section Corner to Sections 18 and 19, T42N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by William A. Burt, U.S. Deputy Surveyor.

Original Corner; Cedar Wood Post

Original Bearing Trees:

Yellow Birch	14"	N 35° E	11 lks (7.26 feet)
Elm	16"	S 40° W	39 lks (25.74 feet)

On October 6, 1851, Guy H. Carleton, U.S. Deputy Surveyor made the following (2) new bearing trees:

Yellow Birch	18"	S 45° E	70 lks (46.20 feet)
Sugar	10"	N 73° W	27 lks (17.82 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

At the corner position, found a 1" diameter iron pin. Iron pin was set by W. E. DeWald, a local mining engineer in the 1960's. Iron pin is consistent with GLO distances North and South along the Range line. I accept the iron pin as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Over the top of the existing iron pin, set a 2" diameter by 30" long split base aluminum pipe monument, with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T42N, R35W, R34W, S-13, S-24, S-18, S-19, 1999, RLS 27457

from which I established the following new blazed and scribed bearing trees:(All measurements taken to a nail in side of tree)

Yellow Birch	9"	N 18° E	10.40 feet
Red Maple	19"	S 46° E	25.37 feet
Balsam	10"	S 49° W	25.50 feet
Power Pole #80-24476		N 36° W	31.68 feet
Steel sign post		East	0.50 feet

99-108

Signed by Gary L. Pisoni

Date 12-28-99

Surveyor's Michigan License No. 27457

PEER GROUP APPROVED

Iron County Rep. 12-21-99
COUNTY REPRESENTATIVE



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 25, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995