

RE

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Iron), Located In, Corner Code #, and numbered sections 1-3 for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

IRON COUNTY MICHIGAN RECEIVED FOR RECORD stamp with date 99 DEC 30 AM 10:29, handwritten notes, and Register of Deeds Stamp & File Number.

4. Lot No. , Recorded Plat
5. Private Claims

Section Corner to Sections 24 and 25, T42N, R35W
Section Corner to Sections 19 and 30, T42N, R34W

I, Gary L. Pisoni, in a field survey on Oct. 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, containing numerical data points for survey locations.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by William A. Burt, U.S. Deputy Surveyor. Original Corner; 14" Sugar Maple Original Bearing Tree: Fir 5" N 20° E 7 lks (4.62 feet)

On October 14, 1851, Guy H. Carleton, U.S. Deputy Surveyor made the following new bearing tree: Sugar 20" S 15° E 70 lks (46.20 feet)

PEER GROUP APPROVED stamp with signature of Iron County Representative dated 12-21-99.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

The corner position is marked by a fence post corner which runs North and East. The fence corner is consistent with GLO distances North and South along the Range line. I accept the fence post corner as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the fence corner, set a 5/8" diameter by 30" long rebar with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T42N, R35W, R34W, S-24, S-25, S-19, S-30, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Table listing bearing trees: Ironwood 7" S 71° E 13.75 feet, Sugar Maple 13" S 25° W 71.97 feet, Sugar Maple 12" S 88° W 19.56 feet, Sugar Maple 8" N 49° W 45.56 feet, Steel sign post N 73° W 0.70 feet.

99-110 Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN. 1993 REVISED OCT., 1995