

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>35W</u>	<u>M-11</u> ✓
	T <u>42N</u> R <u>34W</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:29

L.C. Reynolds: L.S., P. 112

Gary L. Pisoni
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner to Sections 25 and 36, T42N, R35W
Section Corner to Sections 30 and 31, T42N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by William A. Burt, U.S. Deputy Surveyor.

Original Corner; Fir Wood Post

Original Bearing Trees:

Elm	18"	S 27° E	19 lks (12.54 feet)
White Pine	30"	N 21° W	31 lks (20.46 feet)

On October 14, 1851, Guy H. Carleton, U.S. Deputy Surveyor made the following new bearing tree:

Spruce	10"	N 47° E	47 lks (31.02 feet)
--------	-----	---------	---------------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored the corner position at record bearing and distance from the White Pine bearing tree stump which is now 4+ feet in diameter located on the North edge of a farm field. Corner position is approximately 12 feet into the farm field.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 2" diameter by 30" long split base aluminum pipe monument, with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T42N, R35W, R34W, S-25, S-36, S-30, S-31, 1999, RLS 27457

from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Black Cherry	6"	N 40° W	28.76 feet
Maple	8"	N 04° W	58.67 feet
Maple	7"	N 34° E	99.68 feet
Balsam	7"	S 80° E	57.53 feet
Steel sign post		North	1.07 feet

PEER GROUP APPROVED

Iron County Rep 12-21-99
COUNTY REPRESENTATIVE

99-112

Signed by *Gary L. Pisoni*

Date 12-28-99

Surveyor's Michigan License No. 27457

