

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>42N</u> R <u>35W</u>	<u>A7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>42N</u> R <u>35W</u>	<u>12</u>
	S <u>20</u> T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

12 May 17 2006
 A7 May 16 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A7) Corner common to Sections 18 & 19 T42N-R35W and Sections 13 & 24 T42N-R36W. Iron County Peer Group approved corner monumented by D.D.Lappala for the USFS in 1972. See land corner certificate L10 P40, dated 12-21-02 by Gary L. Pisoni PS.
 (12-Sec. 20) Center-south 1/16 corner, Section 20. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A7) Recovered the 1972 USFS monument as described in LCRC L10 P40, and the following bearing trees: 4" Balsam N72E 16.3', scribing visible; 8" Balsam S34E 9.6', scribing visible; 11" Aspen S74W 29.8', overgrown blazes; 6" Aspen N15W 14.4', standing dead; Metal sign post N45E 0.9'; Metal sign post S55W 3.1'. Accepted the monument as a careful and faithful perpetuation of the position of the corner. Cut down the Balsam 8" S34E NBT to facilitate GPS observations. Left the monument in place and made new witnesses as described below.

(12-Sec. 20) Established the corner on the North-South 1/4 line of Section 20, as run in at the mean of the bearings of the East and West lines of Section 20, and at index-corrected record distance of 20.00 chains south of the Center of Section 20. The distance from this corner to the Center of Section 20 (unmonumented) is 1314.61'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A7) Found 2" I.pipe with 3" brass cap. Set measuring nails in the following new bearing trees: 6" Balsam N16E 22.6' mrkd "S18 NBT" 5" Balsam S64E 17.3' mrkd "S19 NBT" Bearings are magnetic. Distances are to nail with tag.	(12) Set 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 9" Sugar N34E 14.9' mrkd "1/16S BT" 4" Sugar S70E 38.7' do 6" Sugar S40W 25.3' do 7" Sugar N85W 18.5' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/13/06

For the Michigan Department of Natural Resources, Office of Land and Facilities