

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>35W</u>	<u>F4</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>42N</u> R <u>35W</u>	<u>11</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		●		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Nov 14 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (F4) Center of Section 9. Not established in the original survey. Found no subsequent record.
- (11-Sec. 9) Southwest 1/16 corner, Section 9. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (F4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
- (11-Sec. 9) Established the corner at the intersection of straight lines connecting opposite 1/16 corners (the Center-West 1/16 corner of Sec. 9 was computed as being midway and on a straight line between corners E4 and F4, both monumented). From the corner thus established, I found a 1" ID iron pipe, placed by persons unknown, N20W 25.9' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (F4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
15" Hemlock N15E 43.9' <i>mrkd "C1/4 BT"</i>
9" Sugar S40E 38.6' <i>do</i>
10" Sugar S46W 38.9' <i>do</i>
11" Sugar N59W 34.5' <i>do</i>
Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag. | (11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
12" Sugar S71E 11.3' <i>mrkd "1/16S BT"</i>
12" Sugar S37W 14.2' <i>do</i>
7" Sugar N84W 10.5' <i>do</i>
8" Sugar N18W 10.7' <i>do</i>
Set sq'd Sugar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/19/05

For the Michigan Department of Natural Resources, Office of Land and Facilities