

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u>	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>42N</u> R <u>35W</u>	<u>H10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>42N</u> R <u>35W</u>	<u>SMC west of H10</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Sep 20 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (H10) Center of Section 27. Not established in the original survey. Found no subsequent record.
- (SMC west of H10) Special meander corner on the left bank of the Brule River on the E-W 1/4 line Section 27. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (H10) Established the corner at the intersection of the North-South 1/4 line, being a straight line between 1/4 corners, and the East-West 1/4 line, established at the mean bearing of the north and south lines of Section 27.
- (SMC west of H10) Established the corner on the E-W 1/4 line of Section 27 at the West bank of the Brule River 1500.48' west of the monumented center of Section 27.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |  |
|--|--|
| (H10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>14" W.Spruce N12E 38.7' mrkd "C1/4 BT"<br>7" Balsam N89E 8.0' do<br>12" Poplar S45W 13.0' do<br>3" W.Spruce S87W 21.1' do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (SMC) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>6" Spruce N21E 10.8' mrkd "SMC BT"<br>11" Spruce N65E 9.7' do<br>8" Spruce S82E 30.9' do<br>11" Spruce S40E 6.7' do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|--|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/10/06