

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>42N</u> R <u>35W</u>	<u>I12</u>
	T <u>42N</u> R <u>35W</u>	<u>I10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Sep 21 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (I12) Quarter corner common to Sections 34 and 35. 1851 - Established by Harvey Mellen, Deputy Surveyor: S15'E between Sections 34 & 35 ...40.00 Set post 1/4 Sec. corner. Cedar 12 S74W 34 links, Cedar 12 S27W 36 links. Found no subsequent record.
- (I10) Quarter corner common to Sections 26 and 27. 1851 - Established by Harvey Mellen, Deputy Surveyor: S15'E between Sections 26 & 27 ...40.00 Set post 1/4 Sec. corner. Spruce 5 S17W 22 links, Tamarac 4 N10E 58 links. ... 80.00 Set post at corner of Secs. 26 27 34 & 35.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (I12) The original post and accessories were not recovered. At the corner position, I found an old E-W fence line at very nearly record distance south of Section corner I11 (GLO=2640', Meas = 2640.95'). This fence runs east along the south side of a meandering trail. I produced the Section line between Sections 26 and 27 and intersected it with this fence, reestablishing the position for the corner at said intersection. I also found remains of another old fence on the section line to the north, between corners I11 and I12.
- (I10) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record between Section corners 2641.07' north and south. There exists an old fence and field line which runs from the corner I11 location to a point which is 193' south and 69' east of the corner monumented.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (I12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: | (I10) Set 1"IDx60" I.pipe with 4" alum. MDNR cap. Set measuring nails in: |
| 4" Balsam N84E 19.8' mrkd "1/4S NBT" | 3" Tamarack N03E 14.2' mrkd "1/4S NBT" |
| 9" Spruce S09W 45.6' do | 5" Tamarack S66E 23.4' do |
| 10" Spruce N39W 28.9' do | 3" Tamarack S18E 15.0' do |
| 11" Spruce N18W 27.1' do | 3" Tamarack S76W 9.1' do |
| Set s'qd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/10/06

For the Michigan Department of Natural Resources, Office of Land and Facilities