

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>43N</u> R <u>R31W</u>	<u>G-4</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

99 DEC 30 AM 10:16

L.C. Record: L. 8, P. 44

*[Signature]*  
REGISTERED DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner to Sections 9 and 10, T43N, R31W

I, Gary L. Pisoni, in a field survey on April 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on June 19, 1849 by John Burt, U.S. Deputy surveyor.  
Original Corner; Yellow Birch Post  
Original Bearing Trees:  
Yellow Birch 12" N 34° E 20 lks (13.20 feet)  
Yellow Birch 12" S 40° W 12 lks (7.92 feet)

PEER GROUP APPROVED  
*Iron Gary L. Pisoni 12-21-99*  
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found an iron pipe located on the East/West quarter line of Section 9 and approximately 33 feet from the centerline of a North/South county road.

Set a P.K. nail at the quarter corner position on line between the Northeast Corner and the Southeast Corner of Section 9 with the extension of the East/West quarter line of Section 9 through the iron pipe to the intersection of the East boundary line of Section 9. The P.K. nail is 2.11 feet North of the single proportionate mathematical position.

Corner position is 2.7 feet East of centerline.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set one (1) reference monument being a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R31W, R.M., 1/4, S-9, S-10, S 34° E, 46.87 feet, 1999, RLS 27457; from which I established the following new reference objects:

Spruce	5"	N 33° E	43.87 feet
Tamarack	10"	S 40° E	28.18 feet
Utility Pole	98-15418	S 16° W	92.62 feet
1/2" pipe		S 89° 54' 07" W	32.32 feet
R.M.	5/8" x 30" rebar	N 34° W	46.87 feet
Steel sign post		S 89° 54' 07" W	32.9 feet

99-44  
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

