

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Iron), Located In (T43N R31W), Corner Code # (G-5), and sections for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

99 DEC 30 AM 10:17
L.C. Records: 2.8, P. 45
[Signature]

Register of Deeds Stamp & File Number

4. Lot No. ... Recorded Plat ...
5. Private Claims ...

Section Corner to Sections 9, 10, 15, 16, T43N, R31W

I, Gary L. Pisoni, in a field survey on April 12, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column G and row 5.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established on June 19, 1849 by John Burt, U.S. Deputy Surveyor.
Original Corner; Cedar Post
Original Bearing Trees:
Spruce 12" N 28°E 20 lks (13.20 feet)
Cedar 12" S 34°W 15 lks (9.90 feet)

PEER GROUP APPROVED
Iron Aug 2, Jan 12-21-99
COUNTY REPRESENTATIVE

On 11/16/73, Arthur O. Enger, RLS, DNR, restored the corner position by proportionate measurement and set a 5" diameter by 36" long re-inforced concrete cylinder with a 3 1/2" aluminum cap stamped as follows: T43N, R31W, S-9, S-10, S-15, S-16, 11/16/73, RLS 13581, recorded in Liber 1, Page 409 of LC records.

1973 Bearing Trees:
Cedar 10" S 51° W 49.2 feet
Cedar 9" N 38° W 43.1 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found

On 4/12/99, found the above described monument located in the West ditch of a North/South county road. I accept the DNR monument as the best available evidence for restoring the corner position.

The following bearing trees found:
Cedar 12" S 50° W 49.41 feet
Cedar 12" N 42° W 43.69 feet
Wood post 5" x 5" N 50° E 0.9 feet
Monument is 23.4 feet West of centerline.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Blazed and scribed the following new bearing tree; (All measurements taken to a nail in side of tree)
Spruce 9" N 81° E 46.01 feet
Steel sign post S 03° W 0.95 feet

99-45
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971
27457 REVISED MAY 19, 1975
REVISED JAN., 1983
REVISED OCT., 1995

